CKa
Christopher Kidd and Associates, LLC
ARCHITECTS   ENGINEERS   PLANNERS

Detail 4 — DUMPSTER ELEVATION
SCALE: 1/4"=1'-0"

- METAL COPING CAP (TYPICAL)
- EIFS TO MATCH BUILDING (TYPICAL)
- PRE-CAST STONE ACCENT BAND (TYPICAL)
- STONE VENEER TO MATCH BUILDING (TYPICAL)
- FOUNDATION BELOW

3'-4" / 6'-0" / 2'-0" / 4'-0"

Detail 5 — DUMPSTER ELEVATION
SCALE: 1/4"=1'-0"

- BALL BEARING BARREL HINGE, (3) PER GATE DOOR, WELD TO STEEL POST AND STEEL TUBE FRAMING (TYPICAL)
- 3" X 3" STEEL TUBE FRAMING (TYPICAL)
- CORRUGATED METAL SHEET (TYPICAL)
- CROSS BRACING BEYOND (TYPICAL)
- METAL COPING CAP (TYPICAL)
- EIFS TO MATCH BUILDING (TYPICAL)
- PRE-CAST STONE ACCENT BAND (TYPICAL)
- STONE VENEER TO MATCH BUILDING (TYPICAL)
- FOUNDATION BELOW
- 4" RUBBER CASTOR WHEEL LOCATED 24" FROM THE EDGE OF THE GATE (TYPICAL FOR 2)
- GATE LATCH AND CANE BOLTS (TYPICAL)

3'-4" / 6'-0" / 2'-0" / 4'-0"

Detail 6 — DUMPSTER ELEVATION
SCALE: 1/4"=1'-0"

- METAL COPING CAP (TYPICAL)
- EIFS TO MATCH BUILDING (TYPICAL)
- PRE-CAST STONE ACCENT BAND (TYPICAL)
- STONE VENEER TO MATCH BUILDING (TYPICAL)
- FOUNDATION BELOW

3'-4" / 6'-0" / 2'-0" / 4'-0"

Detail 2 — SECTION AT GATE
SCALE: 1 1/2"=1'-0"

- 3" X 3" STEEL TUBE FRAMING (TYPICAL)
- CORRUGATED METAL SHEET
- CANE BOLTS

3" / VARIES / 3" / VARIES / VARIES / VARIES / 3" / 5'-5" / 4"

Detail 3 — SECTION AT DUMPSTER ENCLOSURE
SCALE: 1/2"=1'-0"

- METAL COPING CAP ON WOOD BLOCKING
- 2" THICK EIFS
- SMOOTH FACE CAST STONE SILL
- SELF ADHERED WATER RESISTIVE BASE FLASHING WITH MESH WEEPS IN HEAD JOINTS AT 16" OC
- STONE VENEER
- 8" CMU BOND BEAM WITH (1) #5 REBAR
- 8" CMU BACKUP WALL
- 8" CMU BOND BEAM WITH (1) #6 REBAR
- 1/2" PRE-MOLDED JOINT FILLER SET 1/4" BELOW SURFACE-CAULK GAP FLUSH WITH SURFACE
- 8" CONCRETE SLAB
- 12" FREE-DRAINING COMPACTED GRAVEL BASE
- CONCRETE FOUNDATION AND FOOTING

Detail 1 — DUMPSTER ENCLOSURE PLAN
SCALE: 1/4"=1'-0"

NOTES:
1. GRIND SMOOTH ALL WELDS, SMOOTH AND BLEND EDGES FOR ALL METAL ON DOOR ASSEMBLY.
2. ALL GATE SURFACES HARDWARE AND BOLLARDS SHALL BE PAINTED MUSKET GRAY.

- EXTEND HEAVY DUTY REINFORCED PAVING IN FRONT OF ENCLOSURES AS SHOWN - SEE CIVIL DRAWINGS FOR MORE INFORMATION
- 6"Ø x 4'-0" PIPE BOLLARDS (TYPICAL FOR 2)
- 6"Ø x 6'-0" PIPE BOLLARDS FOR GATE MOUNTING (TYPICAL FOR 2)
- CMU CORES GROUTED SOLID WITH #5 REBAR, AT CORNERS AND AT 4'-0" OC (TYPICAL)
- 8" REINFORCED PORTLAND CEMENT CONCRETE SLAB (MIN. 4,000 PSI AT 28 DAYS WITH 6% AIR ENTRAINMENT AND REINFORCED W/ 6x6 W1.4xW1.4 WWF) ON 12" GRANULAR SUBBASE AT DUMPSTER ENCLOSURE, EXTEND CONCRETE SLAB DISTANCE SHOWN BEYOND FRONT OF ENCLOSURE
- 6"Ø x 4'-0" PIPE BOLLARDS (TYPICAL FOR 5)
- PRIME AND PAINT 8" CMU ON INSIDE OF ENCLOSURES (TYPICAL)

20'-0" / 14'-8" / 22'-8" / 2'-4" / 18'-0" / 2'-4" / 2'-2" / 6" / 6" / 2'-4" / 4'-0" / 4'-0" / 4'-0" / 4'-0" / 2'-4"

TYP / OPP

TRASH ENCLOSURE DETAILS

CINCINNATI HOME DIALYSIS - MEDICAL OFFICE BUILDING